

Mobile plant and equipment



Objective

To prevent fatalities, eliminate or minimise the risk of injuries and incidents from working with mobile plant and equipment.

Requirements

At Haslin Constructions:

1. We conduct and document risk assessments to identify all reasonably foreseeable hazards in relation to procurement, modification, operation, transfer, moving, disposal and maintenance of mobile plant and equipment.
2. Where we cannot eliminate the risks, effective and appropriate control measures and procedures are established that are implemented, maintained, monitored and reviewed in line with the hierarchy of controls.
3. We use mobile plant for its designed purpose and within its safe operating limits with consideration of environmental conditions and manufacturer requirements.
4. We plan works to separate people and plant and comply with all road and site rules.
5. We implement an inspection, maintenance and servicing regime in line with manufacturers' requirements to verify that the item of plant is in good condition and safe to operate.
6. We never modify mobile plant and equipment outside the manufacturers' requirements unless it is approved, engineered and certified by a competent person.
7. We ensure that site or task specific requirements and manufacturers' instructions are readily available and communicated to operators, including the provision of any plant specific safety features and hazard information.
8. We establish controls to ensure equipment is only operated by authorised persons.
9. We report and respond to all mobile plant and equipment defects and remove items from service as required.
10. We develop and implement a framework to ensure all operators are competent by providing them with relevant information and instruction on mobile plant and equipment.
11. We ensure persons approving, authorising or supervising work are competent and trained in relevant work procedures.
12. We plan and regularly test emergency and rescue arrangements related to incidents and potential scenarios with mobile plant and equipment.